

# Installation Guide






Zeeff Panel Systems is a leader in customized architectural design solutions for building envelopes.

With extensive experience in the metal panel industry, ZPS has witnessed its evolution firsthand. Today, driven by a renewed vision, we are committed to transforming the industry for the better.

- + Limitless design options
- + Fully tested system
- + Dedicated project team



# INSTALLATION GUIDE

Easy Installation

Non Combustible

No Silicone Sealants

Not Laminated









**Professional Installation Recommended:** Zeeff Panel Systems strongly recommends that all panels be installed by qualified professionals to ensure safety, performance, and compliance with building codes.

**Guidelines Are General Reference Only:** This guide provides general installation instructions and may not address project specific conditions. Always refer to project specifications and consult with the project engineer or architect.

For precise installation requirements and to ensure compliance with project specific conditions, always refer to the approved shop drawings.

#### **Origin Premier**

Origin Premier is a versatile single skin metal panel offering unmatched design flexibility and a wide range of finishes to suit any architectural vision.



Premier Flat
Customize size, material,
thickness and finish



Premier Edge Customize depth, size, material, thickness and finish



Premier Perforated
Customize imagery,
perforation diameter, material,
size, thickness, and finish



Premier Dimension
Customize depth, material, size, thickness and finish



Premier Butterfly

\*Panel requirements can be complex

-Consult ZPS sales team for specific
project request\*

# Premier vs. Select

One System. Multiple Solutions.

Robust detailing, field measurements and installation drawing sets

Ability to color match

Customize your panel size within our size parameters to meet your vision

# PREMIER

Faster shop drawing and production lead times

Ability to custom color match

Wide variety of panel sizes to select from

SELECT

Value Engineered Solution

# Origin Select

Origin Select retains the same quality and performance. The key to its affordability lies in the optimized process with select sizes, making this program an ideal choice for projects that demand both excellence and economic efficiency.



Cut-to-fit application



#### **Premier vs. Select**

Features	Premier	Select
Panel Sizes	Customizable	Standardized
Colors	Unlimited	Standard *Color match as requested
Formed Corners	<b>⊘</b>	8
Brake Metal Trims	<b>⊘</b>	8
Architectural Detailing	<b>Ø</b>	<b>⊘</b>
Cut-to-Fit Detailing	<b>②</b>	8
Field Measurement Drawings	<b>Ø</b>	8
Installation Drawing Set	<b>⊘</b>	*Available if required



#### Step One:

//ZEEFF

//, ZEEFF

// ZEEFF

//, ZEEFF

//ZEEFF

#### Perimeter Trims


Install brake metal trims prior to the small J extrusion. ZPS offers these trims as a valueadded option—please consult your ZPS representative.



#### **Step Two:**

#### Small J Starter Extrusion

Install the small "J" starter engagement is needed.



For precise installation requirements and to ensure compliance with project specific conditions, always refer to the approved shop drawings.

# Step Three:

# Install Panels


Secure the bottom hook and tip in position. Begin installing the panels from the bottom, working left to right.



# **Step Four:**

# Coping Keepers

Fasten the coping cleat before the installation of the coping cap and splice plate.




# **Step Five:**

# Coping Caps and Splice Plates

During installation, insert the splice plate into the coping cap. For integrated coping, secure it directly into the face of the panel's J pocket.

ZPS supplies 6" splice plates when coping is added to a purchase order.






# Step One:

# Drip Flashings (if applicable)


Depending on the project specifications, install the bottom drip flashings first, if necessary.



## **Step Two:**

# Extrusion Backpieces


Install the 2 piece J extrusion backpiece where needed. Drill weep holes as required at the bottom.



# **Step Three:**

#### **Cut Start Extrusion**

Install the cut start extrusion at any location where a panel will interface with an extrusion. (all cut locations)





## Step Four: Field Cut and Install Panels

Field trim panels as needed to accommodate site conditions.

Begin installation at the bottom working left to right..





## **Step Five:**


Field Drill Fastening Holes


Field drill fastening holes at top of panel if top fastening flange has been removed.



# Step Six: Extrusion Caps

Seat extrusion caps into place with a rubber mallet.





# Step Seven:

# Overlap Coping (if applicable)

Install coping keepers, splice plates, and coping cap.

